BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50344

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/15/2021-22, Date: 18-02-2022

Name of Work:Improvements to Footpath and Drains in ward no. 07 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHANKARREDDY KALLEPALLI ( )	
				In Figures	In Words
1	1019.07	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications..	Cum	114.0	Rupees One Hundred Fourteen Only
2	32.76	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification .	Cum	4901.0	Rupees Four Thousand Nine Hundred One Only
3	63.18	1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.	Cum	4043.0	Rupees Four Thousand Forty Three Only
4	28.08	KSRRB M200-5.1: Providing and laying cement concrete of mix 1:2:4 with OPC @ 240 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.63cum and fine aggregates @0.42 cum including cost of materials, labour, HOM curing, form works scaffolding and centering complete as per MORTH section:2200 & IS 456, A) Upto 5mtr height.	Cum	5207.0	Rupees Five Thousand Two Hundred Seven Only
5	117	Providing and fixing 25 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate)	Sqm	4496.0	Rupees Four Thousand Four Hundred Ninety Six Only
6	101.25	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	1939.0	Rupees One Thousand Nine Hundred Thirty Nine Only
7	1019.07	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	78.0	Rupees Seventy Eight Only

K. Sankar Reddy
Signature of the Contractor

Executive Engineer 21/04
Byarayanapura Division
BBMP, Bangalore - 92

21/04